

# Transmission Infrastructure Plan

Briefing to the Portfolio Committee on Electricity and Energy

**Segomoco Scheppers**

04 December 2024





## The Transmission Development Plan has four main objectives



Determine **new network infrastructure requirements** to **integrate new generation capacity** and **address system stability requirements**



Determine **new network infrastructure requirements** to sustain and **allow for future demand growth**



**Consider asset replacement requirements** to ensure **reliability of supply** and **network optimisation**




**Attain Grid Code compliance** by resolving both substation and line violations (N-1)


# TDP overview | Transition from centralised Gx in the north to distributed VRE in south requires grid expansion

Major corridors required

## Future load vs. generation patterns requires transmission infrastructure upgrades




Lower load in the South remains



Generation increase in the South

Significant transmission development is required in the northern, central and southern corridors




## Key insights

- Historically, the architecture the Tx network was designed to dispatch power from the centralised power pools in Mpumalanga and Limpopo to load centres across the country
- The ramping down of some of the baseload coal plants, mainly in Mpumalanga, will likely be replaced with distributed RE, mainly Wind and Solar from the broader Cape regions
- Significant new transmission corridors or lines are required to transport the power from these regions to the load centres in the northern parts of the country
- The transmission infrastructure upgrades must enable security of supply, enable lower cost renewables in optimal resource areas
- Transmission infrastructure typically takes 8-10 years to complete (in line with international standards) and poses a significant risk to SA's energy transition.


# TDP overview | Transition from centralised Gx in the north to distributed VRE in south requires grid expansion

Major corridors required

## Future load vs. generation patterns requires transmission infrastructure upgrades




Lower load in the South remains



Generation increase in the South


Significant transmission development is required in the northern, central and southern corridors



## Key insights

- Historically, the architecture the Tx network was designed to dispatch power from the centralised power pools in Mpumalanga and Limpopo to load centres across the country
- The ramping down of some of the baseload coal plants, mainly in Mpumalanga, will likely be replaced with distributed RE, mainly Wind and Solar from the broader Cape regions
- Significant new transmission corridors or lines are required to transport the power from these regions to the load centres in the northern parts of the country
- The transmission infrastructure upgrades must enable security of supply, enable lower cost renewables in optimal resource areas
- Transmission infrastructure typically takes 8-10 years to complete (in line with international standards) and poses a significant risk to SA's energy transition.


# TDP overview | Summary of infrastructure requirements



## Power Lines (km)

Transmission Assets Nationally	Total New Assets: 2025 - 2029	Total New Assets: 2030 - 2034	Total New Assets: 2025 - 2034
<b>Power lines (km)</b>			
765 kV	767	6190	6957
400 kV	4251	3226	7477
275 kV	26	34	60
<b>Total length (km)</b>	<b>5044</b>	<b>9450</b>	<b>14494</b>

- Solid lines represent existing lines
- Dotted lines represent proposed new lines



## Transformers

Transmission Assets Nationally	Total New Assets: 2025 - 2029	Total New Assets: 2030 - 2034	Total New Assets: 2025 - 2034
<b>Transformers</b>			
<b>Number of Units</b>	<b>87</b>	<b>123</b>	<b>210</b>
<b>Capacity (MVA)</b>	<b>41325</b>	<b>91325</b>	<b>132650</b>



## Reactors

Transmission Assets Nationally	Total New Assets: 2025 - 2029	Total New Assets: 2030 - 2034	Total New Assets: 2025 - 2034
<b>Reactors</b>			
<b>Number of Units</b>	<b>14</b>	<b>45</b>	<b>59</b>
<b>Capacity (MVar)</b>	<b>3260</b>	<b>13000</b>	<b>16260</b>



## Synchronous Condensers

Synchronous Condensers to be installed at 7 substations


The transmission grid is central to security of supply and advancing the just energy transition



## Capacitors

Transmission Assets Nationally	Total New Assets: 2025 - 2029	Total New Assets: 2030 - 2034	Total New Assets: 2025 - 2034
<b>Capacitors</b>			
<b>Number of Units</b>	<b>15</b>	<b>25</b>	<b>40</b>
<b>Capacity (MVar)</b>	<b>1032</b>	<b>1660</b>	<b>2692</b>

# TDP overview | NTCSA needs to deliver a step change in infrastructure rollout, with most of this occurring in Phase 2



Source: TDP 2024

## Transmission Lines


- ~14 500 km of lines to be installed over 2025 to 2034
- ~5X greater than the actual installation over 2015-2024
- Phase 2 is ~ 2X larger than Phase 1

## Transformers

- ~133 000 MVA required by 2034
- ~10 X greater than the actual installation over 2015-2024
- Phase 2 is ~ 2X larger than Phase 1


# TDP overview | 2 phases for TDP: Phase 1 maximises existing corridors, whilst Phase 2 requires new 765 kV corridors

## Phase 1: Maximise & augment current corridors (2025-2029)



**Generation:** ~30 GW new connection capacity from 2024  
**Demand:** Peak demand increases to 39 GW from 34 GW in 2024

## Phase 2: Install 2x 765 kV corridors (2030-2034)




**Generation:** ~26 GW new connection capacity from 2029  
**Demand:** Peak demand increases to ~43 GW in 2034






# TDP pipeline | Projects are ready for execution through to 2029, with remaining projects in development

**Transmission lines**  
(km)



**Transformer capacity**  
('000 MVA)



Under Development Ready for Execution Target

## Tx lines

### Ready for Execution

- 15 projects (~ 1 700 km) ready for or already under execution

### In development

- 29 projects (~3 300 km) under various stages of development

## Transformer Capacity

### Ready for Execution

- 28 projects (~17 500 MVA) ready for or already under execution

### In development

- 36 projects (~24 000 MVA) under development
- Transformer projects have a shorter development cycle compared to Transmission lines

**Project adds connect new generation and demand and ensure reliability**

## 1. EPCM

- Historically NTCSA has utilised the project delivery strategy of EPCM (Engineer, Procure and Construction Management) for both expansion and refurbishment projects.
- NTCSA is responsible for, manages the full PLCM (from concept to implementation) and secures its own funding.

## 2. Self-Build

- NTCSA may approve a self-build methodology where a private company will build transmission infrastructure or project and possibly transfer back to NTCSA.

## 3. EPC / OE

- The EPC and OE strategies were adopted to supplement the internal resource capacity. A decision was taken to incorporate these strategies for TDP projects.
- Allows NTCSA to reduce the number of contracts to be managed and to further supplement TDP execution.

## 4. PSPs

- Private Sector Participation (PSP) emerged as potential alternative delivery mechanism.
- NTCSA investigating possible private sector participation in collaboration with Government

---

**~60%**  
*of the TDP physicals (MVA's and km)*

---

**~40%**  
*of the TDP physicals (MVA's and km)*



## Acquiring Land and servitude rights

- Landowner holdouts prevent projects from being commenced or energized; Projects are being escalated to Ministry and NECOM for increased focus



## Servitude encroachment & access

- Land parcels that are secured on the route may have informal housing encroaching, creating both a safety risk and preventing project teams from accessing Tx lines
- Projects are being escalated to NECOM for increased focus



## Line construction capacity

- Local industry on capable of 800 km p.a., with requirement reaching 1 600 km by 2028 already.
- Incubation program started, 2 companies already graduated
- OE panel contract has been established
- EPC Lines Engineering panel contract has been established



## Large Transformers

- Local supply capacity is adequate for Class 1 & 2
- One single supplier for Class 3b. No local supplier for Class 4.
- NTCSA has pre-qualified 22 international factories, up from 8 by the beginning of 2022.
- 101 transformer panel contract Class 3b transformers
- Initiated development of new enabling agreement that has not yet been issued – to cater for all transformer classes.




## Steel

- The country has one supplier of fabricated structural steel
- RFI issued to the market for structural steel for powerlines to determine the capability and capacity of the local industry.
- 6 Steel suppliers invited to prepare prototype towers
  - 2 suppliers completed the prototype in Oct 2024
  - 4 suppliers planned final prototypes inspection is Dec 2024



- The key drivers for new transmission infrastructure are associated with:
  - An increase in **new generation capacity** mainly in areas with limited grid thereby requiring substantial grid expansions to transport the power to load centres across the country
  - Ensuring the **reliability** of the interconnected power system
  - **Sustaining** the existing transmission asset base to meet the current and future demand growth
- The TDP highlights the requirement of ~14,500 km of additional transmission lines (5,000 km by 2029) and ~133 000MVA transformer capacity (~41 000 MVA by 2029) by 2034, as well as several refurbishment projects.
- Corporate Plan had made provision for R112 billion (revision in progress) for the first 5-year period of the TDP up to 2029. Delivery will be dependent on revenue/tariff application through NERSA, mobilization of capital, contractors, suppliers and skilled workers and professionals.
- Maintaining **system security** and **stability**, due to large scale renewable energy integration, will increasingly become a challenge into the future and is being addressed by the introduction of synchronous condensers at strategic locations on the transmission grid
- Several **challenges** to delivering on the TDP 2024 have been identified and actions are already in progress to address them (along with initiatives to alleviate grid constraints in the short term)
- The implementation of the TDP 2024 is critical to the security of energy supply, advancing the just energy transition and economic growth



Thank you